

Heard County, Georgia

ADDENDUM # 1

March 14, 2024

Heard County RFB Asphalt Resurfacing – Multiple Roads

This addendum is issued to change or clarify the proposal documents associated with the
Heard County RFB for Asphalt Resurfacing – Multiple Roads
Issued February 28, 2024

List of Items Included in Addendum #1

1. Questions and Answers (attached)

**Note: A signed acknowledgement of this addendum must be received by the
Purchasing Agent attached to your response.**

Vendor Name: _____

Address: _____

Email: _____

Authorized Signature: _____ Date: _____

Name (Printed): _____ Title: _____

- Q1 On page 19 the last paragraph tells of Liquidated Damages for not completion the work, the first paragraph on page 20 tell of the same thing, the only problem is that there are different Liquidated Damage amounts listed for each paragraph. Which one is correct?
- A1 Both. Substantial Completion and Final Completion (Punch List Complete)
- Q2 Can you please provide the Road Widths for each road listed on page 17?
- A2 Frolona 24ft, Boggus 20ft, Joe Stephens 21ft, Pea Ridge 20ft, West Ferry 21ft.
- Q3 Our guess is that you only intend to apply the Leveling @ 55 lbs/sy to certain roads, which roads on page 17 will get this leveling work scope?
- A3 Boggus Road
- Q4 Will the Leveling be applied over the entire length and width of each of the roads?
- A4 Boggus Rd only, entire length and width
- Q5 Can we assume that Portable Advanced Warning Signs can be used during construction activities or do you want to spend extra money for Post Mounted Signs?
- A6 Portable Signs are acceptable
- Q7 Can we assume that the County will perform any/all of the Shoulder Backfilling, Low/Soft Shld Signs and Grassing work required, once the paving is completed by the Contractor?
- A7 Yes
- Q8 Will there be any Lane Closure Restrictions, or can we work whenever we want?
- A8 No Restrictions
- Q9 What is you expectation for the Contractor to begin the actual work? Approximate Notice to Proceed Date?
- A9 April 2024
- Q10 How many days should the Contractor expect to wait after the completion of the paving before the final pavement markings are installed? Typically GDOT used 30-45 Days to allow the new pavement to cure.
- A10 30-45 Days
- Q11 We assume that the County expects the Contractor to install Temporary Pavement Markings immediately after the asphalt paving is completed, is this correct?
- A11 Yes

Q12 Does the County expect the Contractor to utilize a Shuttle Buggy for the placement of any of the asphalt? If so, which roads and which mixes will a Shuttle Buggy be required?

A12 Shuttle Buggy to be used on all roads.

Q13 Will the Contractor be allowed to Run the Gate out on adjacent Side Roads and Driveways for the new pavement tie ins?

A13 Yes